CITY OF KNOB NOSTER, MISSOURI

Request for Proposal (RFP) Addendum

Addendum No.: 1 Date of Addendum: August 13, 2024

Due Date: 4:00 PM, August 16, 2024

Title: Knob Noster 2024 Sidewalk Construction Project

SCOPE OF ADDENDUM

This addendum details additions to the RFP based on the questions received. Revisions to preexisting language are indicated either by strikethrough for deletions and underlining for insertions.

Revision 1 ADDITION

STORMWATER PIPE IN PROJECT AREA

There is an underground stormwater pipe in the scope of the project area. The pipe will need to be removed by the contractor. An additional line for the pipe removal has been added to the attached bid sheet.

Revision 2 ADDITION

POWER POLES IN PROJECT AREA

The City believes that the power poles adjacent to the project area will not interfere with the construction of the sidewalk. If it has been determined by the selected contractor that the project is not feasible without relocation of the poles, then the City will work with the contractor and Evergy to adjust the scope of the project.

Revision 3 ADDITION

RELOCATION OF CITY STREET SIGN

The City will relocate all signage as necessary.

Revision 4 ADDITION

REMOVAL OF OVERHANGING LIMBS AND BRUSH

The City will handle the trimming of any necessary trees and brush in the project area.

Revision 5 ADDITION

DISTANCE OF RIGHT OF WAY AND GRADING LIMITS

The City assumes the distance of the Right-of-Way for the project area to be Thirty (30) feet from the center line of the road, according to existing plats. Additional surveying may be necessary.

Revision 6 ADDITION

DISTANCE BETWEEN SIDEWALK AND CURB

A minimum of two (2) feet is required between the sidewalk and the curb.

Revision 7 CLARIFICATION

CONCRETE CURB AND GUTTER

The City is requesting the construction of Type S 18" concrete curb and gutter, per the drawing attached with the original RFP.

This addendum shall become part of the RFP and MUST be returned with the RFP.

RESPONDER	
NAME:	
SIGNATURE:	
TITLE:	
DATE:	

ITEM	DESCRIPTION	QUANTITY	<u>UNIT</u>	UNIT COST	TOTAL COST	
1.00	Start Up, Mobilization, Miscellaneous					
1.01	Mobilization/Demobilization	1	L.S.	\$	\$	
	\$					
2.00	Sidewalk and Traffic Calming Improvements	1				
2.01	Unclassified Excavation, Disposal and Compacted Backfills and replacements.	1	L.S.	\$		
2.02	4" Thick Concrete Sidewalk w/ 4" of 1" Rolled Stone Base	175	S.Y.	\$	\$	
2.03	18" Concrete Curb and Gutter (6" Thick) w/ 4" of 1" Rolled Stone Base	280	L.F.	\$	\$	
2.04	6" Concrete Pavement (Sidewalk approaches) w/ 4" of 1" Rolled Stone Base	30	S.Y.	\$	\$	
2,05	Driveway Transition Grading & Rock	30	S.Y.			
2.05	Erosion Control/Silt Fence	300	L,F,	\$	\$	
2.06	Detectable Warnings	2	EA.	\$	\$	
2.07	Traffic Control	1	L.S.	\$.\$	
2.09	Finished grading, seeding, and mulching	1	L.S.	\$	\$	
2.10	Removal of Existing Plastic Stormwater Pipe	280	L.F.	\$	\$	
Subtotal for Item 2.00: Sidewalk Improvements \$						
	\$					